



SHARP ESTIMATES

MATERIAL TAKE-OFFS

Material List For: Example Job

Page 1 of 7

	Name	Qty	Units
01 1ST FL WALLS			
<u>01</u>	STUDS	1-3/4X5-1/2-24' LSL (VERIFY)	15.00 EA
<u>01</u>	WALL BRACING SM	2X4-12' #3 YP	181.00 EA
<u>01</u>	STUDS	2X4-128 5/8" KD FJ PINE	379.00 EA
<u>01</u>	WALL BRACING SM	2X4-14' #3 YP	3.00 EA
<u>01</u>	STUDS	2X4-140 5/8" KD FJ PINE	14.00 EA
<u>01</u>	BOTTOM PLATE	2X4-16' #2 BORATE	27.00 EA
<u>01</u>	TOP PLATES	2X4-16' #2 SPF	57.00 EA
<u>01</u>	STUDS	2X6-128 5/8" KD FJ PINE	498.00 EA
<u>01</u>	STUDS	2X6-140 5/8" KD FJ PINE	30.00 EA
<u>01</u>	BOTTOM PLATE	2X6-16' #2 BORATE	37.00 EA
<u>01</u>	TOP PLATES	2X6-16' #2 SPF	96.00 EA
<u>01</u>	SILL SEALER	3 1/2" X 50' ROLL	10.00 EA
<u>01</u>	SILL SEALER	5 1/2" X 50' ROLL	14.00 EA
<u>02</u>	PORCH BEAM	1-3/4 X 11-7/8" LVL @ 19'	6.00 EA
<u>02</u>	HEADER	1-3/4 X 18" LVL @ 17'	3.00 EA
<u>02</u>	PORCH BEAM	1-3/4 X 20" LVL 2.0E 3100 @ 27'	3.00 EA

01 1ST FL WALLS

<u>03</u>	GDH	1-3/4 X 16" LVL @ 20'	3.00	EA
<u>03</u>	GDH	2X12 #2 YP @ 12'	3.00	EA
<u>04</u>	HEADER	2X12 #2 YP @ 10'	12.00	EA
<u>04</u>	HEADER	2X12 #2 YP @ 12'	5.00	EA
<u>04</u>	HEADER	2X12 #2 YP @ 8'	13.00	EA
<u>04</u>	PORCH BEAM	2X12 #2 YP' @ 10'	8.00	EA
<u>04</u>	PORCH BEAM	2X12 #2 YP' @ 12'	6.00	EA
<u>05</u>	HEADER	2X10 #2 YP @ 10'	2.00	EA
<u>05</u>	HEADER	2X10 #2 YP @ 8'	3.00	EA
<u>06</u>	HEADER	2X8 #2 YP @ 12'	15.00	EA
<u>06</u>	HEADER	2X8 #2 YP @ 16'	3.00	EA
<u>06</u>	HEADER	2X8 #2 YP @ 8'	3.00	EA
<u>07</u>	HEADER	2X6 #2 YP @ 12'	20.00	EA
<u>08</u>	EXT. HEADER SPACER	1/2" FOAM BOARD	4.00	EA

02 1ST FL CEILING JOIST

<u>01</u>	RIDGE BEAM	1-3/4 X 14" LVL @ 22'	3.00	EA
<u>01</u>	FLOAT BEAM	2X12 #2 YP @ 14'	4.00	EA
<u>02</u>	CEILING JOIST	2X8 #2 YP @ 14'	17.00	EA
<u>03</u>	CEILING JOIST	2X6 #2 YP @ 10'	8.00	EA
<u>03</u>	CEILING JOIST	2X6 #2 YP @ 12'	20.00	EA

02 1ST FL CEILING JOIST

<u>03</u>	CEILING JOIST	2X6 #2 YP @ 16'	12.00	EA
<u>03</u>	CEILING JOIST	2X6 #2 YP @ 8'	53.00	EA
<u>04</u>	FALSE RAFTERS	2X6 #2 YP @ 10'	32.00	EA
<u>06</u>	HANGER	LU26	30.00	EA
<u>06</u>	SKEWED HANGER	SUR/L26 (VERIFY)	32.00	EA

03 2ND FL WALLS

<u>01</u>	STUDS	2X4-116 5/8" KD FJ PINE	357.00	EA
<u>01</u>	WALL BRACING SM	2X4-12' #3 YP	132.00	EA
<u>01</u>	BOTTOM-TOP PLATES	2X4-16' #2 SPF	72.00	EA
<u>01</u>	STUDS	2X6-116 5/8" KD FJ PINE	313.00	EA
<u>01</u>	BOTTOM-TOP PLATES	2X6-16' #2 SPF	63.00	EA
<u>02</u>	2ND FL ADHESIVE	28 OZ ADHESIVE	52.00	EA
<u>02</u>	STRINGERS	2X12-20' #2 YP	10.00	EA
<u>02</u>	RISER	2X8-20' #2 YP (PER PLAN DETAIL)	6.00	EA
<u>02</u>	2ND FL DECKING	3/4" 4X8 ADVANTECH	104.00	EA
<u>03</u>	HEADER	1-3/4 X 14" LVL @ 15'	3.00	EA
<u>04</u>	HEADER	2X12 #2 YP @ 16'	3.00	EA
<u>05</u>	HEADER	2X10 #2 YP @ 10'	6.00	EA
<u>06</u>	HEADER	2X8 #2 YP @ 8'	10.00	EA
<u>07</u>	HEADER	2X6 #2 YP @ 12'	21.00	EA

03 2ND FL WALLS

<u>08</u>	EXT. HEADER SPACER	1/2" FOAM BOARD	3.00	EA
-----------	--------------------	-----------------	------	----

04 2ND FL CEILING JOIST

<u>01</u>	BEAM	1-3/4 X 14" LVL @ 14'	3.00	EA
-----------	------	-----------------------	------	----

<u>01</u>	BEAM	2X12 #2 YP @ 16'	4.00	EA
-----------	------	------------------	------	----

<u>01</u>	BEAM	2X12 #2 YP @ 18'	6.00	EA
-----------	------	------------------	------	----

<u>02</u>	FLOAT BEAM	2X12 #2 YP @ 12'	2.00	EA
-----------	------------	------------------	------	----

<u>02</u>	FLOAT BEAM	2X12 #2 YP @ 16'	4.00	EA
-----------	------------	------------------	------	----

<u>02</u>	FLOAT BEAM	2X12 #2 YP @ 18'	4.00	EA
-----------	------------	------------------	------	----

<u>02</u>	FLOAT BEAM	2X12 #2 YP @ 20'	6.00	EA
-----------	------------	------------------	------	----

<u>03</u>	CEILING JOIST	2X12 #2 YP @ 12'	2.00	EA
-----------	---------------	------------------	------	----

<u>03</u>	CEILING JOIST	2X12 #2 YP @ 16'	3.00	EA
-----------	---------------	------------------	------	----

<u>03</u>	CEILING JOIST	2X12 #2 YP @ 20'	27.00	EA
-----------	---------------	------------------	-------	----

<u>04</u>	CEILING JOIST	2X10 #2 YP @ 18'	9.00	EA
-----------	---------------	------------------	------	----

<u>05</u>	CEILING JOIST	2X8 #2 YP @ 16'	25.00	EA
-----------	---------------	-----------------	-------	----

<u>06</u>	CEILING JOIST	2X6 #2 YP @ 10'	11.00	EA
-----------	---------------	-----------------	-------	----

<u>06</u>	CEILING JOIST	2X6 #2 YP @ 12'	43.00	EA
-----------	---------------	-----------------	-------	----

<u>06</u>	CEILING JOIST	2X6 #2 YP @ 8'	38.00	EA
-----------	---------------	----------------	-------	----

<u>07</u>	HANGER	LJ210	10.00	EA
-----------	--------	-------	-------	----

<u>07</u>	HANGER	LU26	35.00	EA
-----------	--------	------	-------	----

<u>07</u>	HANGER	U210-3	4.00	EA
-----------	--------	--------	------	----

04 2ND FL CEILING JOIST

05 ROOF

<u>01</u>	HIP/VALLEY	2X10 #2 YP @ 16'	3.00	EA
<u>01</u>	HIP/VALLEY	2X10 #2 YP @ 18'	2.00	EA
<u>01</u>	RIDGE	2X12 #2 YP @ 20'	1.00	EA
<u>01</u>	RAFTERS	2X8 #2 YP @ 10'	4.00	EA
<u>01</u>	RAFTERS	2X8 #2 YP @ 12'	25.00	EA
<u>01</u>	RAFTERS	2X8 #2 YP @ 8'	4.00	EA
<u>02</u>	RIDGE	2X10 #2 YP @ 12'	1.00	EA
<u>02</u>	RIDGE	2X10 #2 YP @ 14'	4.00	EA
<u>02</u>	RIDGE	2X10 #2 YP @ 16'	7.00	EA
<u>02</u>	RIDGE	2X10 #2 YP @ 18'	3.00	EA
<u>02</u>	RIDGE	2X10 #2 YP @ 20'	1.00	EA
<u>02</u>	RIDGE	2X10 #2 YP @ 22'	1.00	EA
<u>02</u>	RIDGE	2X10 #2 YP @ 8'	1.00	EA
<u>03</u>	HIP/VALLEY	2X8 #2 YP @ 10'	2.00	EA
<u>03</u>	HIP/VALLEY	2X8 #2 YP @ 12'	1.00	EA
<u>03</u>	HIP/VALLEY	2X8 #2 YP @ 14'	3.00	EA
<u>03</u>	HIP/VALLEY	2X8 #2 YP @ 16'	6.00	EA
<u>03</u>	HIP/VALLEY	2X8 #2 YP @ 18'	4.00	EA
<u>03</u>	HIP/VALLEY	2X8 #2 YP @ 20'	7.00	EA

05 ROOF

<u>03</u>	HIP/VALLEY	2X8 #2 YP @ 22'	1.00	EA
<u>03</u>	HIP/VALLEY	2X8 #2 YP @ 8'	1.00	EA
<u>04</u>	LEDGER	2X8 #2 YP' @ 12'	1.00	EA
<u>04</u>	LEDGER	2X8 #2 YP' @ 14'	1.00	EA
<u>04</u>	LEDGER	2X8 #2 YP' @ 24'	1.00	EA
<u>04</u>	LEDGER	2X8 #2 YP' @ 26'	1.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 10'	29.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 12'	71.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 14'	51.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 16'	25.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 18'	19.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 20'	49.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 22'	7.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 24'	2.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 26'	1.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 28'	2.00	EA
<u>05</u>	RAFTERS	2X6 #2 YP @ 8'	31.00	EA
<u>06</u>	BRACING-COLLAR TIE	2X4-16' #3 YP	240.00	EA
<u>06</u>	BRACING-STIFF BACKS	2X6-16' #3 YP	45.00	EA

06 CORNICE

06 CORNICE

<u>01</u>	1ST FL WALL SHEATHING	1/2" 4X9 OX-IS	147.00	EA
<u>01</u>	CORNER WRAP	18" X 120' MOISTOP 12 MILL	3.00	EA
<u>01</u>	BRICK LEDGE	18" X 150' MOISTOP 30 MILL	1.00	EA
<u>01</u>	SEAM TAPE	2-7/8" X 165' DOW WEATHERMATE	24.00	EA
<u>02</u>	2ND FL WALL SHEATHING	1/2" 4X10 ZIP WALL	72.00	EA
<u>02</u>	SHEATHING TAPE	3.75" X 90' ZIP TAPE	26.00	EA
<u>02</u>	WINDOW SILL TAPE	6" X 75' ZIP STRETCH TAPE	3.00	EA
<u>03</u>	ATTIC DECKING	3/4" 4X8 TG OSB (VERIFY AMOUNT)	35.00	EA
<u>03</u>	ROOF DECKING	7/16" 4X8 OSB	280.00	EA
<u>03</u>	ROOF CLIPS	7/16" CLIPS (250 PER BOX)	7.00	EA
<u>04</u>	SOFFIT	1X12-12' SMOOTH HARDIE NON-VENTED	50.00	EA
<u>04</u>	FRIEZE	1X4-12' SMOOTH HARDIE	56.00	EA
<u>04</u>	FASCIA	1X6-12' SMOOTH HARDIE	56.00	EA
<u>05</u>	BUILD OUTS	1X4-16' #3 YP	45.00	EA
<u>05</u>	SOFFIT FRAME	2X4-16' UTILITY	60.00	EA
<u>05</u>	RAFTER TIES	H2.5A	270.00	EA
<u>05</u>	HOLDOWNS	HTT45	4.00	EA